

BILL OF QUANTITIES

ELECTRICAL POWER DISTRIBUTION WORKS

PROJECT DETAILS

Project	Proposed B+G+8+R Commercial & Residential Building
Owner	Qutaiba Ameen Abdal Kija
Plot No.	6731315 — Al Barsha South Third, Dubai, UAE
Architect	Engr. Samer Mahmoud Ajami (Reg. 105181)
Structural	Engr. Mohamad Maher Myaser Jabban (Reg. 101079)
Consultant	Future Art Engineering Consultancy
Job No.	FA_P379 / CRs B/010/25
Drawing Ref	P-001 ... P-300 (14 sheets, Power Layout)
Drawing Date	16.01.2026
BOQ Date	05/05/2026
Authority	DEWA (Dubai Electricity & Water Authority)

BUILDING ELECTRICAL LOAD

Total Connected Load (TCL)	2117.06 kW
Demand Factor	0.75
Maximum Demand (MD)	~1597 kW

RECONCILIATION NOTES — corrections applied vs source data

- LVP-01 !' SMDB-1F...8F risers sized at 4C × 150mm² (PDF wins; XLSX source had 300mm², which is oversized for the 256 A load).
- Fire-pump feeder sized at 1×4C 185mm² FR + 1C 95mm² ECC (PDF wins; XLSX source had 2×4C 300mm² FR, which is oversized for 167 A start).
- ESMDB-G feeder sized at 4C × 300mm² FR (XLSX wins; PDF source had a 70mm² value in section 4 vs 300mm² in section 8.7 — 70mm² is undersized by ~3× for the 338 A load).
- Building totals on Cover (TCL 2,117.06 kW · MD ~1,597 kW · DF 0.80) sourced from comparison PDF — no load_summary in live extraction.
- Rate column F populated with INDICATIVE Dubai 2026 rates from scripts/lib/dubai-2026-rates.mjs. Review and adjust to actual supplier quotations before tender submission.

STATUS: PRICED (INDICATIVE) — Dubai 2026 market rates · review before submission

SECTION A — LV SWITCHGEAR & SUB-MAIN DISTRIBUTION BOARDS

Project: Proposed B+G+8+R Commercial & Residential Building, Plot 6731315 | Job: FA_P379 / CRs B/010/25

Item	Description	Reference	Unit	Qty	Rate (AED)	Amount (AED)	Remarks
A1 — LV Panels & Main Switchgear							
A1.1	LVP-01: 3P+N+E, 415V, floor-standing LV switchboard with 2000A main ACB, busbars, metering. Outgoing: 8× 300A!'SMDB-1F..8F.	SLD	Nr	1			LVP-01 main
A1.2	Capacitor Bank — 375 kVAR, 415V, automatic PF correction for LVP-01.	SLD	Nr	1			LVP-01 PF c
A1.3	LVP-02: 3P+N+E, 415V, floor-standing LV switchboard with 1600A main ACB, busbars, metering. Outgoing: 1× 500A!'SMDB-RF, 1× 160A!'SMDB-EV, 1× 125A!'SMDB-G, 12× 50A!'SMDB-SH01..12, 1× 400A!'ESMDB-G, 1× 350A!'Fire Pump.	SLD	Nr	1			LVP-02 main panel
A1.4	Capacitor Bank — 275 kVAR, 415V, automatic PF correction for LVP-02.	SLD	Nr	1			LVP-02 PF c
A1.5	Automatic Transfer Switch (ATS) Panel — 415V, 400A, 4P. Complete with controls and interlocking.	SLD	Nr	1			Mains/Gen c
A1.6	Standby Generator — 300 kVA, diesel, weatherproof canopy, AMF panel, fuel tank, exhaust. Complete installed and commissioned.	SLD	Nr	1			Backu p
Sub-Total A1						—	
A2 — SMDBs (Typical Floors)							
A2.1	SMDB-1F: Floor-standing SMDB, 300A TP MCCB incomer, outgoing MCCBs as per SLD. Connected load: 150.86 kW.	SLD	Nr	1			1F
A2.2	SMDB-2F: Floor-standing SMDB, 300A TP MCCB incomer, outgoing MCCBs as per SLD. Connected load: 150.86 kW.	SLD	Nr	1			2F
A2.3	SMDB-3F: Floor-standing SMDB, 300A TP MCCB incomer, outgoing MCCBs as per SLD. Connected load: 150.86 kW.	SLD	Nr	1			3F
A2.4	SMDB-4F: Floor-standing SMDB, 300A TP MCCB incomer, outgoing MCCBs as per SLD. Connected load: 150.86 kW.	SLD	Nr	1			4F
A2.5	SMDB-5F: Floor-standing SMDB, 300A TP MCCB incomer, outgoing MCCBs as per SLD. Connected load: 150.86 kW.	SLD	Nr	1			5F
A2.6	SMDB-6F: Floor-standing SMDB, 300A TP MCCB incomer, outgoing MCCBs as per SLD. Connected load: 150.86 kW.	SLD	Nr	1			6F
A2.7	SMDB-7F: Floor-standing SMDB, 300A TP MCCB incomer, outgoing MCCBs as per SLD. Connected load: 150.86 kW.	SLD	Nr	1			7F
A2.8	SMDB-8F: Floor-standing SMDB, 300A TP MCCB incomer, outgoing MCCBs as per SLD. Connected load: 150.86 kW.	SLD	Nr	1			8F
Sub-Total A2						—	
A3 — SMDBs (Ground/Roof/Services/Emergency)							
A3.1	SMDB-TF-odd: SMDB with 300A TP MCCB incomer, outgoing MCCBs as per SLD.	SLD	Nr	4			1F/3F/5F/7F
A3.2	SMDB-TF-even: SMDB with 300A TP MCCB incomer, outgoing MCCBs as per SLD.	SLD	Nr	4			2F/4F/6F/8F
A3.3	SMDB-RF: SMDB with 500A TP MCCB incomer, outgoing MCCBs as per SLD.	SLD	Nr	1			Roof — 248
A3.4	SMDB-G: SMDB with 125A TP MCCB incomer, outgoing MCCBs as per SLD.	SLD	Nr	1			Ground —
A3.5	SMDB-EV: SMDB with 160A TP MCCB incomer, outgoing MCCBs as per SLD.	SLD	Nr	1			Basem ent —
A3.6	SMDB-SH01: SMDB with 40A TP MCCB incomer, outgoing MCCBs as per SLD.	SLD	Nr	1			Ground —
A3.7	SMDB-SH02: SMDB with 40A TP MCCB incomer, outgoing MCCBs as per SLD.	SLD	Nr	1			Ground —
A3.8	SMDB-SH03: SMDB with 40A TP MCCB incomer, outgoing MCCBs as per SLD.	SLD	Nr	1			Ground —

Item	Description	Reference	Unit	Qty	Rate (AED)	Amount (AED)	Remarks
A3.9	SMDB-SH04: SMDB with 40A TP MCCB incomer, outgoing MCCBs as per SLD.	SLD	Nr	1			Ground —
A3.10	SMDB-SH05: SMDB with 40A TP MCCB incomer, outgoing MCCBs as per SLD.	SLD	Nr	1			Ground —
A3.11	SMDB-SH06: SMDB with 40A TP MCCB incomer, outgoing MCCBs as per SLD.	SLD	Nr	1			Ground —
A3.12	SMDB-SH07: SMDB with 40A TP MCCB incomer, outgoing MCCBs as per SLD.	SLD	Nr	1			Ground —
A3.13	SMDB-SH08: SMDB with 40A TP MCCB incomer, outgoing MCCBs as per SLD.	SLD	Nr	1			Ground —
A3.14	SMDB-SH09: SMDB with 40A TP MCCB incomer, outgoing MCCBs as per SLD.	SLD	Nr	1			Ground —
A3.15	SMDB-SH10: SMDB with 40A TP MCCB incomer, outgoing MCCBs as per SLD.	SLD	Nr	1			Ground —
A3.16	SMDB-SH11: SMDB with 40A TP MCCB incomer, outgoing MCCBs as per SLD.	SLD	Nr	1			Ground —
A3.17	SMDB-SH12: SMDB with 63A TP MCCB incomer, outgoing MCCBs as per SLD.	SLD	Nr	1			Ground —
A3.18	ESMDB-G: SMDB with 400A TP MCCB incomer, outgoing MCCBs as per SLD.	SLD	Nr	1			Ground — 1
A3.19	ESMDB-RF: SMDB with 160A TP MCCB incomer, outgoing MCCBs as per SLD.	SLD	Nr	1			Roof —
Sub-Total A3						—	
SECTION A — TOTAL						—	

SECTION B — DISTRIBUTION BOARDS (DBS) & CONSUMER UNITS

Project: Proposed B+G+8+R Commercial & Residential Building, Plot 6731315 | Job: FA_P379 / CRs B/010/25

Item	Description	Reference	Unit	Qty	Rate (AED)	Amount (AED)	Remarks
B1 — Distribution Boards							
B1.1	DB-G: DB fed from SMDB-G, 63A TP incomer.	SLD	Nr	1			Groun
B1.2	DB-F1: DB fed from SMDB-G, 40A TP incomer.	SLD	Nr	1			Groun
B1.3	DB-F4: DB fed from SMDB-G, 40A TP incomer.	SLD	Nr	1			Groun
B1.4	DB-F5: DB fed from SMDB-G, 40A TP incomer.	SLD	Nr	1			Groun
B1.5	DB-L.GYM: DB fed from SMDB-RF, 40A TP incomer.	SLD	Nr	1			Roof
B1.6	DB-G.GYM: DB fed from SMDB-RF, 40A TP incomer.	SLD	Nr	1			Roof
B1.7	DB-WM: DB fed from SMDB-RF, 40A TP incomer.	SLD	Nr	1			Roof
B1.8	EDB-G: DB fed from ESMDB-G, 40A TP incomer.	SLD	Nr	1			Groun
B1.9	EDB-1F: DB fed from ESMDB-G, 32A TP incomer.	SLD	Nr	1			1F
B1.10	EDB-TEL: DB fed from ESMDB-G, 40A TP incomer.	SLD	Nr	1			Groun
B1.11	EDB-PR: DB fed from ESMDB-G, 40A TP incomer.	SLD	Nr	1			Under
B1.12	EDB-4F: DB fed from ESMDB-RF, 40A TP incomer.	SLD	Nr	1			4F
B1.13	EDB-7F: DB fed from ESMDB-RF, 40A TP incomer.	SLD	Nr	1			7F
B1.14	EDB-GSM-R: DB fed from ESMDB-RF, 40A TP incomer.	SLD	Nr	1			Roof
B1.15	DB-T01 to DB-T15 (odd floors): DB fed from SMDB-TF-odd, 40A TP incomer.	SLD	Nr	1			1F/3F/5F/7F
B1.16	DB-T01 to DB-T15 (even floors): DB fed from SMDB-TF-even, 40A TP incomer.	SLD	Nr	1			2F/4F/6F/8F
B1.17	DB-SHOP01 to DB-SHOP12: DB fed from SMDB-SH01 to SMDB-SH12, TP incomer.	SLD	Nr	1			Groun d
Sub-Total B1						—	
SECTION B — TOTAL						—	

SECTION C — LV POWER CABLES — MAIN & RISING MAINS

Project: Proposed B+G+8+R Commercial & Residential Building, Plot 6731315 | Job: FA_P379 / CRs B/010/25

Item	Description	Reference	Unit	Qty	Rate (AED)	Amount (AED)	Remarks
C1 — XLPE/SWA/PVC LV Cables							
C1.1	4C × 150mm ² XLPE/SWA/PVC armoured — LVP-01 to SMDB-1F (4C 150mm ² XLPE/SWA/PVC +1x1x70mm ² ECC). Incl. glands, lugs, terminations.	SLD	m	25			
C1.2	4C × 150mm ² XLPE/SWA/PVC armoured — LVP-01 to SMDB-2F (4C 150mm ² XLPE/SWA/PVC +1x1x70mm ² ECC). Incl. glands, lugs, terminations.	SLD	m	29			
C1.3	4C × 150mm ² XLPE/SWA/PVC armoured — LVP-01 to SMDB-3F (4C 150mm ² XLPE/SWA/PVC +1x1x70mm ² ECC). Incl. glands, lugs, terminations.	SLD	m	33			
C1.4	4C × 150mm ² XLPE/SWA/PVC armoured — LVP-01 to SMDB-4F (4C 150mm ² XLPE/SWA/PVC +1x1x70mm ² ECC). Incl. glands, lugs, terminations.	SLD	m	37			
C1.5	4C × 150mm ² XLPE/SWA/PVC armoured — LVP-01 to SMDB-5F (4C 150mm ² XLPE/SWA/PVC +1x1x70mm ² ECC). Incl. glands, lugs, terminations.	SLD	m	41			
C1.6	4C × 150mm ² XLPE/SWA/PVC armoured — LVP-01 to SMDB-6F (4C 150mm ² XLPE/SWA/PVC +1x1x70mm ² ECC). Incl. glands, lugs, terminations.	SLD	m	45			
C1.7	4C × 150mm ² XLPE/SWA/PVC armoured — LVP-01 to SMDB-7F (4C 150mm ² XLPE/SWA/PVC +1x1x70mm ² ECC). Incl. glands, lugs, terminations.	SLD	m	49			
C1.8	4C × 150mm ² XLPE/SWA/PVC armoured — LVP-01 to SMDB-8F (4C 150mm ² XLPE/SWA/PVC +1x1x70mm ² ECC). Incl. glands, lugs, terminations.	SLD	m	53			
C1.9	4C × 185mm ² XLPE/SWA/PVC armoured — LVP-01 to SMDB-TF-odd (1X4C 185mm ² XLPE/SWA/PVC +1C 95mm ² ECC). Incl. glands, lugs, terminations.	SLD	m	45			
C1.10	4C × 185mm ² XLPE/SWA/PVC armoured — LVP-01 to SMDB-TF-even (1X4C 185mm ² XLPE/SWA/PVC +1C 95mm ² ECC). Incl. glands, lugs, terminations.	SLD	m	45			
C1.11	4C × 150mm ² XLPE/SWA/PVC armoured — LVP-02 to SMDB-RF (2X4C 150mm ² XLPE/SWA/PVC +1X1C 150mm ² ECC). Incl. glands, lugs, terminations.	SLD	m	65			
C1.12	4C × 50mm ² XLPE/SWA/PVC armoured — LVP-02 to SMDB-G (1X4C 50mm ² XLPE/SWA/PVC +1X1C 25mm ² ECC). Incl. glands, lugs, terminations.	SLD	m	15			
C1.13	4C × 70mm ² XLPE/SWA/PVC armoured — LVP-02 to SMDB-EV (1X4C 70mm ² XLPE/SWA/PVC +1X1C 35mm ² ECC). Incl. glands, lugs, terminations.	SLD	m	20			
C1.14	4C × 10mm ² XLPE/SWA/PVC armoured — LVP-02 to SMDB-SH01 (1X4C 10mm ² XLPE/SWA/PVC). Incl. glands, lugs, terminations.	SLD	m	20			
C1.15	4C × 10mm ² XLPE/SWA/PVC armoured — LVP-02 to SMDB-SH02 (1X4C 10mm ² XLPE/SWA/PVC). Incl. glands, lugs, terminations.	SLD	m	22			
C1.16	4C × 10mm ² XLPE/SWA/PVC armoured — LVP-02 to SMDB-SH03 (1X4C 10mm ² XLPE/SWA/PVC). Incl. glands, lugs, terminations.	SLD	m	24			
C1.17	4C × 10mm ² XLPE/SWA/PVC armoured — LVP-02 to SMDB-SH04 (1X4C 10mm ² XLPE/SWA/PVC). Incl. glands, lugs, terminations.	SLD	m	26			
C1.18	4C × 10mm ² XLPE/SWA/PVC armoured — LVP-02 to SMDB-SH05 (1X4C 10mm ² XLPE/SWA/PVC). Incl. glands, lugs, terminations.	SLD	m	28			
C1.19	4C × 10mm ² XLPE/SWA/PVC armoured — LVP-02 to SMDB-SH06 (1X4C 10mm ² XLPE/SWA/PVC). Incl. glands, lugs, terminations.	SLD	m	30			

Item	Description	Reference	Unit	Qty	Rate (AED)	Amount (AED)	Remarks
C1.20	4C × 10mm² XLPE/SWA/PVC armoured — LVP-02 to SMDB-SH07 (1X4C 10mm2 XLPE/SWA/PVC). Incl. glands, lugs, terminations.	SLD	m	32			
C1.21	4C × 10mm² XLPE/SWA/PVC armoured — LVP-02 to SMDB-SH08 (1X4C 10mm2 XLPE/SWA/PVC). Incl. glands, lugs, terminations.	SLD	m	34			
C1.22	4C × 10mm² XLPE/SWA/PVC armoured — LVP-02 to SMDB-SH09 (1X4C 10mm2 XLPE/SWA/PVC). Incl. glands, lugs, terminations.	SLD	m	36			
C1.23	4C × 10mm² XLPE/SWA/PVC armoured — LVP-02 to SMDB-SH10 (1X4C 10mm2 XLPE/SWA/PVC). Incl. glands, lugs, terminations.	SLD	m	38			
C1.24	4C × 10mm² XLPE/SWA/PVC armoured — LVP-02 to SMDB-SH11 (1X4C 10mm2 XLPE/SWA/PVC). Incl. glands, lugs, terminations.	SLD	m	40			
C1.25	4C × 16mm² XLPE/SWA/PVC armoured — LVP-02 to SMDB-SH12 (1X4C 16mm2 XLPE/SWA/PVC). Incl. glands, lugs, terminations.	SLD	m	42			
Sub-Total C1						—	
C2 — Fire-Rated (FR) Cables							
C2.1	4C × 300mm² Fire-Rated (BS6387 CWZ) — LVP-02 to ESMD-B-G (4C 300mm2 FIRE RATED +1C 35mm2 ECC).	SLD	m	15			
C2.2	4C × 185mm² Fire-Rated (BS6387 CWZ) — LVP-02 to Fire Pump (1X4C 185mm2 FP400 FIRE RATED +1C 95mm2 FR ECC, 350A TP).	SLD	m	35			
Sub-Total C2						—	
SECTION C — TOTAL						—	

SECTION D — LV POWER CABLES — DISTRIBUTION (SMDB!'DB)

Project: Proposed B+G+8+R Commercial & Residential Building, Plot 6731315 | Job: FA_P379 / CRs B/010/25

Item	Description	Reference	Unit	Qty	Rate (AED)	Amount (AED)	Remarks
D1 — XLPE/SWA/PVC Distribution Cables							
D1.1	4C × 16mm² XLPE/SWA/PVC — SMDB-G to DB-G.	SLD	m	20			
D1.2	4C × 10mm² XLPE/SWA/PVC — SMDB-G to DB-F1.	SLD	m	15			
D1.3	4C × 10mm² XLPE/SWA/PVC — SMDB-G to DB-F4.	SLD	m	15			
D1.4	4C × 10mm² XLPE/SWA/PVC — SMDB-G to DB-F5.	SLD	m	15			
D1.5	4C × 10mm² XLPE/SWA/PVC — SMDB-RF to DB-L.GYM.	SLD	m	20			
D1.6	4C × 10mm² XLPE/SWA/PVC — SMDB-RF to DB-G.GYM.	SLD	m	20			
D1.7	4C × 10mm² XLPE/SWA/PVC — SMDB-RF to DB-WM.	SLD	m	15			
D1.8	4C × 16mm² XLPE/SWA/PVC — SMDB-TF-odd to DB-T01 to DB-T15 odd floors.	SLD	m	25			
D1.9	4C × 16mm² XLPE/SWA/PVC — SMDB-TF-even to DB-T01 to DB-T15 even floors.	SLD	m	25			
Sub-Total D1							—
D2 — Emergency Distribution Cables (FR)							
D2.1	4C × 70mm² Fire-Rated — ESMDB-G to ESMDB-RF.	SLD	m	65			
D2.2	4C × 10mm² Fire-Rated — ESMDB-G to EDB-G.	SLD	m	15			
D2.3	4C × 6mm² Fire-Rated — ESMDB-G to EDB-1F.	SLD	m	25			
D2.4	4C × 10mm² Fire-Rated — ESMDB-G to EDB-TEL.	SLD	m	15			
D2.5	4C × 10mm² Fire-Rated — ESMDB-G to EDB-PR.	SLD	m	30			
D2.6	4C × 10mm² Fire-Rated — ESMDB-RF to EDB-4F.	SLD	m	20			
D2.7	4C × 10mm² Fire-Rated — ESMDB-RF to EDB-7F.	SLD	m	10			
D2.8	4C × 10mm² Fire-Rated — ESMDB-RF to EDB-GSM-R.	SLD	m	15			
D2.9	4C × 10mm² Fire-Rated — ESMDB-RF to Lift-01.	SLD	m	35			
D2.10	4C × 10mm² Fire-Rated — ESMDB-RF to Lift-02.	SLD	m	35			
D2.11	4C × 10mm² Fire-Rated — ESMDB-RF to Lift-03.	SLD	m	35			
D2.12	4C × 10mm² Fire-Rated — ESMDB-RF to Booster Pump.	SLD	m	20			
Sub-Total D2							—
SECTION D — TOTAL							—

SECTION E — CABLE MANAGEMENT — TRAYS, LADDERS & CONDUITS

Project: Proposed B+G+8+R Commercial & Residential Building, Plot 6731315 | Job: FA_P379 / CRs B/010/25

Item	Description	Reference	Unit	Qty	Rate (AED)	Amount (AED)	Remarks
E1 — Cable Trays, Ladders & Conduits							
E1.1	GI Hot-dip galvanised cable ladder, 500mm × 100mm side rail (vertical riser shaft, UG to Roof), c/w supports, brackets, bends, tees, fixings.	SLD	m	40			
E1.2	GI Hot-dip galvanised cable ladder, 300mm × 100mm side rail (horizontal at each floor riser! SMDB), c/w supports, brackets, bends, tees, fixings.	SLD	m	130			
E1.3	GI perforated cable tray, 200mm × 50mm (corridor distribution 1F–8F), c/w supports, brackets, bends, tees, fixings.	SLD	m	400			
E1.4	GI perforated cable tray, 100mm × 50mm (branch distribution to DBs), c/w supports, brackets, bends, tees, fixings.	SLD	m	300			
E1.5	GI perforated cable tray, 200mm × 50mm (Ground floor retail/ common), c/w supports, brackets, bends, tees, fixings.	SLD	m	100			
E1.6	GI perforated cable tray, 300mm × 75mm (Roof mechanical), c/w supports, brackets, bends, tees, fixings.	SLD	m	80			
E1.7	25mm uPVC conduit c/w draw wire, saddles, junction boxes, c/w supports, brackets, bends, tees, fixings.	SLD	m	535			
E1.8	32mm uPVC conduit (cable tray to SMDB at each floor), c/w supports, brackets, bends, tees, fixings.	SLD	m	80			
E1.9	20mm uPVC conduit (final-circuit drops to outlets), c/w supports, brackets, bends, tees, fixings.	SLD	m	400			
E1.10	25mm GI rigid conduit — fire-rated for emergency cable routes (staircase wells, fire shafts), c/w supports, brackets, bends, tees, fixings.	SLD	m	200			
Sub-Total E1							—
SECTION E — TOTAL							—

SECTION F — EARTHING & BONDING

Project: Proposed B+G+8+R Commercial & Residential Building, Plot 6731315 | Job: FA_P379 / CRs B/010/25

Item	Description	Reference	Unit	Qty	Rate (AED)	Amount (AED)	Remarks
F1 — Main Earthing System							
F1.1	Main earth bar (MEB) in LV room — 50×6mm copper busbar, drilled and labelled, c/w insulators and fixing	SLD	Nr	2			
F1.2	Earth pit (BS 7430 / DEWA) — 1200mm copper-bonded steel earth rod, inspection chamber, backfill, conductor clamp. Test < 1 Ω	SLD	Nr	4			
F1.3	1C × 95mm² bare copper earth conductor — MEB to earth pits and DEWA earth terminal	SLD	m	30			
F1.4	1C × 50mm² green/yellow PVC earth conductor — MEB to structural steel bonding points, water/gas entry	SLD	m	40			
F1.5	1C × 35mm² green/yellow XLPE earth conductor — MEB to sub-earth bar at each SMDB	SLD	m	400			
F1.6	1C × 10mm² green/yellow PVC earth conductor — SMDB earth bar to each DB on residential floors	SLD	m	600			
F1.7	Supplementary bonding conductor 4mm² — pipework, trays, equipment frames (provisional)	SLD	Item	1			
Sub-Total F1							—
SECTION F — TOTAL							—

SECTION G — SUNDRIES, ACCESSORIES & TESTING/COMMISSIONING

Project: Proposed B+G+8+R Commercial & Residential Building, Plot 6731315 | Job: FA_P379 / CRs B/010/25

Item	Description	Reference	Unit	Qty	Rate (AED)	Amount (AED)	Remarks
G1 — Accessories & Sundries							
G1.1	Cable identification labels — self-adhesive ferrules at both ends.	—	Item	1			
G1.2	Cable cleats and ties — stainless steel, max 400mm vertical / 900mm horizontal.	—	Item	1			
G1.3	Fire stopping — intumescent compounds, collars, pillows at fire-rated penetrations.	—	Item	1			
G1.4	Smoke / fire barriers at electrical-riser floor penetrations.	—	Nr	12			
G1.5	Temporary power supply during construction — provisional sum.	—	Sum	1			
Sub-Total G1							—
G2 — Testing & Commissioning							
G2.1	Insulation resistance testing (500V Megger) — full report.	DEWA/IEC	Item	1			
G2.2	Continuity and polarity testing of all circuits.	DEWA/IEC	Item	1			
G2.3	Earth fault loop impedance testing at all boards.	DEWA/IEC	Item	1			
G2.4	RCD testing at all RCD-protected circuits.	DEWA/IEC	Item	1			
G2.5	ATS changeover testing — simulate mains failure, verify switchover.	DEWA/IEC	Item	1			
G2.6	Power factor correction verification — record before/after.	DEWA/IEC	Item	1			
G2.7	Full DEWA inspection and approval — provisional sum.	DEWA/IEC	Sum	1			
G2.8	As-built drawings (AutoCAD + PDF) and O&M Manuals.	DEWA/IEC	Item	1			
Sub-Total G2							—
SECTION G — TOTAL							—

BILL OF QUANTITIES — SUMMARY

Proposed B+G+8+R Commercial & Residential Building | Plot 6731315, Al Barsha South Third, Dubai, UAE | FA_P379 / CRs B/010/25

Section	Description	Sheet Ref	Sub-Total (AED)	No of Items
A	LV Switchgear & SMDBs	Sheet A	—	6
B	Distribution Boards & Consumer Units	Sheet B	—	5
C	LV Cables — Main & Rising Mains	Sheet C	—	5
D	LV Cables — Distribution	Sheet D	—	5
E	Cable Management	Sheet E	—	4
F	Earthing & Bonding	Sheet F	—	5
G	Sundries & Testing/Commissioning	Sheet G	—	4
SUB-TOTAL (Sections A–G)			—	
Contingency (10%)			—	
VAT (5%)			—	
GRAND TOTAL (incl. Contingency & VAT)			—	

INSTRUCTIONS: Pricing happens in the paired XLSX. The PDF mirrors the layout for review/print only — Rate and Amount columns are intentionally blank.