

KEO INTERNATIONAL CONSULTANTS

HVAC Equipment Schedule — Al Zahra Commercial Tower

Document: KEO-AZT-HVAC-ES-001 Rev: A | Date: March 2026

VRF OUTDOOR UNIT SCHEDULE

VRF-ODU-01 to 06 | Roof Level A | VRF Outdoor (Heat Recovery) | 16 HP each | Qty: 6 | Daikin VRV-X / Mitsubishi City Multi
VRF-ODU-07 to 12 | Roof Level B | VRF Outdoor (Heat Recovery) | 16 HP each | Qty: 6 | Daikin VRV-X / Mitsubishi City Multi
FAHU-01 to 04 | Each 5th floor AHU room | Fresh Air Handling Unit | 6.0 TR each | Qty: 4 | Carrier / Zamil
EF-01 to 18 | Toilet/pantry shafts | Inline Duct Exhaust Fan | 300 CFM each | Qty: 18 | S&P / Kruger
SEF-01, 02 | Basement parking | Axial Smoke Extract Fan | 25,000 CFM each | Qty: 2 | Systemair / Woods
FCU-L1 to L3 | Ground Floor Lobby | Ceiling Cassette FCU | 3.5 TR each | Qty: 3 | Daikin / Carrier

APPROVED MAKES

VRF System	Daikin, Mitsubishi Electric, LG, Samsung
FAHU	Carrier, Zamil, SKM, Al Salem Johnson Controls
Exhaust Fans	S&P, Kruger, Systemair, Greenheck
Ductwork	Pre-insulated (PIR): Premdor, P3ducto, Ductoseal
Controls	Honeywell, Siemens, Johnson Controls
Copper Piping	Mueller, Cambridge-Lee, Kembla
Insulation	Armaflex, K-Flex (19mm for piping, 25mm for duct)

